SHEET--1 OF 5

SCALE--1 : 300

Block :BLOCK 1 (BLOCK 1)

Floor Name	Total Built Up Area (Sq.mt.)	Deductions (Area in Sq.mt.) StairCase	Lift	Lift Machine	Void	Proposed FAR Area (Sq.mt.) Resi.	Total FAR Area (Sq.mt.)	Tnmt (No.)
Terrace Floor	140.94	130.74	0.00	10.20	0.00	0.00	0.00	00
Fourth Floor	3094.30	63.00	10.20	0.00	236.10	2785.00	2785.00	23
Third Floor	3094.30	63.00	10.20	0.00	236.10	2785.00	2785.00	23
Second Floor	3094.30	63.00	10.20	0.00	236.10	2785.00	2785.00	23
First Floor	2966.76	63.00	10.20	0.00	290.41	2603.15	2603.15	21
Ground Floor	2999.13	63.00	10.20	0.00	227.15	2698.78	2698.78	21
Total:	15389.73	445.74	51.00	10.20	1225.86	13656.93	13656.93	111
Total Number of Same Blocks :	1							
Total:	15389.73	445.74	51.00	10.20	1225.86	13656.93	13656.93	111

SCHEDULE OF JOINERY:


BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
BLOCK 1 (BLOCK 1)	D1	1.00	2.10	111

SCHEDULE OF JOINERY:

BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
BLOCK 1 (BLOCK 1)	W1	2.00	1.20	259

UnitBUA Table for Block :BLOCK 1 (BLOCK 1)

FLOOR	Name	UnitBUA Type	UnitBUA Area	Carpet Area	No. of Rooms	No. of Tenement
GROUND FLOOR PLAN	B1-001	FLAT	73.73	73.73	1	
	B1-002	FLAT	70.31	70.31	1	
	B1-003	EWS UNIT	47.31	47.31	1	
	B1-004	EWS UNIT	47.31	47.31	1	
	B1-005	EWS UNIT	47.31	47.31	1	
	B1-006	EWS UNIT	47.31	47.31	1	
	B1-007	EWS UNIT	47.90	47.90	1	
Total	-	-	10482.23	10482.23	111	111



SITE PLAN

SCHEDULE OF JOINERY:

BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
BLOCK 2 (BLOCK 2)	W2	1.50	1.20	98
BLOCK 2 (BLOCK 2)	W1	1.70	1.20	573
BLOCK 2 (BLOCK 2)	W1	2.00	1.20	04
BLOCK 2 (BLOCK 2)	W1	2.30	1.20	04

SCHEDULE OF JOINERY:

BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
BLOCK 3 SOUTH AND WEST WING (BLOCK 3 SOUTH AND WEST WING)	D1	1.00	2.10	215

SCHEDULE OF JOINERY:

BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
BLOCK 3 SOUTH AND WEST WING (BLOCK 3 SOUTH AND WEST WING)	W1	2.00	1.20	618

Block :BLOCK 3 SOUTH AND WEST WING (BLOCK 3 SOUTH AND WEST WING)

Floor Name	Total Built Up Area (Sq.mt.)	Deductions (Area in Sq.mt.) StairCase	Lift	Lift Machine	Void	Proposed FAR Area (Sq.mt.) Resi.	Total FAR Area (Sq.mt.)	Tnmt (No.)
Terrace Floor	151.69	137.29	0.00	14.40	0.00	0.00	0.00	00
Fourth Floor	6582.94	100.80	24.60	0.00	488.82	5967.72	5967.72	44
Third Floor	6582.94	100.80	24.60	0.00	488.82	5967.72	5967.72	44
Second Floor	6582.94	100.80	24.60	0.00	488.82	5967.72	5967.72	44
First Floor	6582.94	100.80	24.60	0.00	488.86	5967.68	5967.68	44
Ground Floor	6525.20	100.80	24.60	0.00	448.55	5960.25	5960.25	39
Total:	33008.65	641.29	123.00	14.40	2408.87	29821.09	29821.09	215
Total Number of Same Blocks :	1							
Total:	33008.65	641.29	123.00	14.40	2408.87	29821.09	29821.09	215

UnitBUA Table for Block :BLOCK 2 (BLOCK 2)

FLOOR	Name	UnitBUA Type	UnitBUA Area	Carpet Area	No. of Rooms	No. of Tenement
Total	-	-	12036.90	12036.90	370	122

UnitBUA Table for Block :BLOCK 3 SOUTH AND WEST WING (BLOCK 3 SOUTH AND WEST WING)

FLOOR	Name	UnitBUA Type	UnitBUA Area	Carpet Area	No. of Rooms	No. of Tenement
GROUND FLOOR PLAN	B3/S-001	FLAT	114.83	114.83	1	39
	B3/S-002	FLAT	114.82	114.82	1	
	B3/S-003	FLAT	114.82	114.82	1	
	B3/S-004	FLAT	114.82	114.82	1	
	B3/S-005	FLAT	120.54	120.54	1	
	B3/S-006	FLAT	120.45	120.45	1	
	B3/S-007	FLAT	105.09	105.09	1	
	B3/S-008	FLAT	115.74	115.74	1	
	B3/S-009	FLAT	89.32	89.32	1	
	B3/S-010	FLAT	89.32	89.32	1	
	B3/S-011	FLAT	89.32	89.32	1	
	B3/S-012	FLAT	89.31	89.31	1	
	B3/S-013	FLAT	89.31	89.31	1	
	B3/S-014	FLAT	89.31	89.31	1	
	B3/S-015	FLAT	89.31	89.31	1	
	B3/S-016	FLAT	115.74	115.74	1	
	B3/S-017	FLAT	124.50	124.50	1	
	B3/S-018	FLAT	115.14	115.14	1	
	B3-001	FLAT	114.43	114.43	1	
	B3-002	FLAT	126.70	126.70	1	
	B3-003	FLAT	120.77	120.77	1	
	B3-004	FLAT	119.75	119.75	1	
	B3-005	FLAT	132.96	132.96	1	
	B3-006	FLAT	121.55	121.55	1	
	B3-007	FLAT	121.48	121.48	1	
	B3-008	FLAT	121.52	121.52	1	
	B3-009	FLAT	121.52	121.52	1	
	B3-010	FLAT	121.80	121.80	1	
	B3-011	FLAT	121.78	121.78	1	
	B3-012	FLAT	122.31	122.31	1	
	B3-013	FLAT	120.35	120.35	1	
	B3-014	FLAT	121.31	121.31	1	
	B3-015	FLAT	119.84	119.84	1	
	B3-016	FLAT	88.65	88.65	1	
	B3-017	FLAT	88.65	88.65	1	
	B3-018	FLAT	88.65	88.65	1	
	B3-019	FLAT	88.02	88.02	1	
	B3-020	FLAT	88.02	88.02	1	
	B3-021	FLAT	88.02	88.02	1	
FIRST FLOOR PLAN	B3/S-101	FLAT	114.83	114.83	1	44
	B3/S-102	FLAT	114.82	114.82	1	
	B3/S-103	FLAT	114.82	114.82	1	
	B3/S-104	FLAT	114.82	114.82	1	
	B3/S-105	FLAT	120.54	120.54	1	
	B3/S-106	FLAT	120.45	120.45	1	
	B3/S-107	FLAT	105.09	105.09	1	
	B3/S-108	FLAT	115.74	115.74	1	
	B3/S-109	FLAT	89.32	89.32	1	
	B3/S-110	FLAT	89.32	89.32	1	
	B3/S-111	FLAT	89.32	89.32	1	
	B3-219	FLAT	88.02	88.02	1	
	B3-220	FLAT	88.02	88.02	1	
	B3-221	FLAT	88.02	88.02	1	
Total	-	-	23151.87	23151.87	215	215

Block :BLOCK 2 (BLOCK 2)

Floor Name	Total Built Up Area (Sq.mt.)	Deductions (Area in Sq.mt.) StairCase	Lift	Lift Machine	Void	Ramp	Parking	Proposed FAR Area (Sq.mt.) Resi.	Total FAR Area (Sq.mt.)	Tnmt (No.)	Carpet Area other than Tenement
Terrace Floor	126.61	118.41	0.00	10.20	0.00	0.00	0.00	0.00	0.00	00	0.00
Fourth Floor	3378.34	50.40	10.20	0.00	314.89	0.00	0.00	3002.85	3002.85	25	0.00
Third Floor	3378.34	50.40	10.20	0.00	314.89	0.00	0.00	3002.85	3002.85	25	0.00
Second Floor	3378.34	50.40	10.20	0.00	314.89	0.00	0.00	3002.85	3002.85	25	0.00
First Floor	3378.34	50.40	8.40	0.00	314.88	0.00	0.00	3004.66	3004.66	25	0.00
Ground Floor	3168.15	50.40	10.20	0.00	288.67	0.00	0.00	2818.88	2818.88	22	0.00
Basement First Floor	20255.98	214.20	45.00	0.00	0.00	177.29	17583.83	2235.66	2235.66	00	2260.86
Basement Second Floor	9443.35	100.80	20.40	0.00	0.00	324.30	8997.86	0.00	0.00	00	0.00
Total:	46509.45	685.41	114.60	10.20	1548.22	501.59	26581.69	17067.75	17067.75	122	2260.86
Total Number of Same Blocks :	1										
Total:	46509.45	685.41	114.60	10.20	1548.22	501.59	26581.69	17067.75	17067.75	122	2261

Approval Condition :

This Plan Sanction is issued subject to the following conditions :

1.The sanction is accorded for.
a).Consisting of 'Block - BLOCK 1 (BLOCK 1) Wing - BLOCK 1-1 (BLOCK 1) Consisting of 1BASEMENT+GF+4UF and
Block - BLOCK 2 (BLOCK 2) Wing - BLOCK 2-1 (BLOCK 2) Consisting of BASEMENT SECOND, BASEMENT FIRST, GF+4UF and
Block - BLOCK 3 SOUTH AND WEST WING (BLOCK 3 SOUTH AND WEST WING) Wing - BLOCK 3 SOUTH AND WEST WING-1 (BLOCK 3 SOUTH AND WEST WING) Consisting of 2 BASEMENT+GF+4UF'.

2.The sanction is accorded for MultiDwelling Units BLOCK 1 (BLOCK 1) and MultiDwelling Units BLOCK 2 (BLOCK 2) and MultiDwelling Units BLOCK 3 SOUTH AND WEST WING (BLOCK 3 SOUTH AND WEST WING) only. The use of the building shall not deviate to any other use.

3.Car Parking reserved in the plan should not be converted for any other purpose.

4.Development charges towards increasing the capacity of water supply, sanitary and power main has to be paid to BWSSB and BESCOM if any.

5.Necessary ducts for running telephone cables, cubicles at ground level for postal services & space for dumping garbage within the premises shall be provided.

6.The applicant shall construct temporary toilets for the use of construction workers and it should be demolished after the construction.

7.The applicant shall INSURE all workmen involved in the construction work against any accident / untoward incidents arising during the time of construction.

8.The applicant shall not stock any building materials / debris on footpath or on roads or on drains. The debris shall be removed and transported to near by dumping yard.

9.The applicant / builder is prohibited from selling the setback area / open spaces and the common facility areas, which shall be accessible to all the tenants and occupants.

10.The applicant shall provide a space for locating the distribution transformers & associated equipment as per K.E.R.C (Es& D) code leaving 3.00 mts. from the building within the premises.

11.The applicant shall provide a separate room preferably 4.50 x 3.65 m in the basement for installation of telecom equipment and also to make provisions for telecom services as per Bye-law No. 25.

12.The applicant shall maintain during construction such barricading as considered necessary to prevent dust, debris & other materials endangering the safety of people / structures etc. in & around the site.

13.Permission shall be obtained from forest department for cutting trees before the commencement of the work.

14.License and approved plans shall be posted in a conspicuous place of the licensed premises. The building license and the copies of sanctioned plans with specifications shall be mounted on a frame and displayed and they shall be made available during inspections.

15.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the Architect / Engineer / Supervisor will be informed by the Authority in the first instance, warned in the second instance and cancel the registration if the same is repeated for the third time.

16.Technical personnel, applicant or owner as the case may be shall strictly adhere to the duties and responsibilities specified in Schedule - IV (Bye-law No. 3.6) under sub section IV-8 (e) to (k).

17.The building shall be constructed under the supervision of a registered structural engineer.

18.On completion of foundation or footings before erection of walls on the foundation and in the case of columnar structure before erecting the columns "COMMENCEMENT CERTIFICATE" shall be obtained.

19.Construction or reconstruction of the building should be completed before the expiry of five years from the date of issue of license & within one month after its completion shall apply for permission to occupy the building.

20.The building should not be occupied without obtaining "OCCUPANCY CERTIFICATE" from the competent authority.

21.Drinking water supplied by BWSSB should not be used for the construction activity of the building.

22.The applicant shall ensure that the Rain Water Harvesting Structures are provided & maintained in good repair for storage of water for non potable purposes or recharge of ground water at all times having a minimum total capacity mentioned in the Bye-law 32(a).

23.The building shall be designed and constructed adopting the norms prescribed in National Building Code and in the "Criteria for earthquake resistant design of structures" bearing No. IS 1893-2002 published by the Bureau of Indian Standards making the building resistant to earthquake.

24.The applicant should provide solar water heaters as per table 17 of Bye-law No. 29 for the building.

25.Facilities for physically handicapped persons prescribed in schedule XI (Bye laws - 31) of Building bye-laws 2003 shall be ensured.

26.The applicant shall provide at least one common toilet in the ground floor for the use of the visitors / servants / drivers and security men and also entrance shall be approached through a ramp for the Physically Handicapped persons together with the stepped entry.

27.The Occupancy Certificate will be considered only after ensuring that the provisions of conditions vide Sl. No. 23, 24, 25 & 26 are provided in the building.

28.The applicant shall ensure that no inconvenience is caused to the neighbors in the vicinity of construction and that the construction activities shall stop before 10.00 PM and shall not resume the work earlier than 7.00 AM to avoid hindrance during late hours and early morning hours.

29.Garbage originating from Apartments / Commercial buildings shall be segregated into organic and inorganic waste and should be processed in the Recycling processing unit ---- k.g capacity installed at site for its re-use / disposal (Applicable for Residential units of 20 and above and 2000 Sqm and above built up area for Commercial building).

30.The structures with basement/s shall be designed for structural stability and safety to ensure for soil stabilization during the course of excavation for basement/s with safe design for retaining walls and super structure for the safety of the structure as well as neighboring property, public roads and footpaths, and besides ensuring safety of workman and general public by erecting safe barricades.

31.The Builder / Contractor / Professional responsible for supervision of work shall not shall not materially and structurally deviate the construction from the sanctioned plan, without previous approval of the authority. They shall explain to the owner s about the risk involved in contravention of the provisions of the Act, Rules, Bye-laws, Zoning Regulations, Standing Orders and Policy Orders of the BBMP.

32.The construction or reconstruction of a building shall be commenced within a period of two (2) years from date of issue of licence. Before the expiry of two years, the Owner / Developer shall give intimation to BBMP (Sanctioning Authority) of the intention to start work in the form prescribed in Schedule VI. Further, the Owner / Developer shall give intimation on completion of the foundation or footing of walls / columns of the foundation. Otherwise the plan sanction deemed cancelled.

33.In case of Development plan, Parks and Open Spaces area and Surface Parking area shall be earmarked and reserved as per Development Plan issued by the Bangalore Development Authority.

34.All other conditions and conditions mentioned in the work order issued by the Bangalore Development Authority while approving the Development Plan for the project should be strictly adhered to

35.The Applicant / Owner / Developer shall abide by the collection of solid waste and its segregation as per solid waste management bye-law 2016.

36.The applicant/owner/developer shall abide by sustainable construction and demolition waste management as per solid waste management bye-law 2016.

37.The Applicant / Owners / Developers shall make necessary provision to charge electrical vehicles.

38.The Applicant / Owner / Developer shall plant one tree for a) sites measuring 180 Sqm up to 240 Sqm b) minimum of two trees for sites measuring with more than 240 Sqm. c) One tree for every 240 Sqm of the FAR area as part thereof in case of Apartment / group housing / multi-dwelling unit/development plan.

39.In case of any false information, misrepresentation of facts, or pending court cases, the plan sanction is deemed cancelled.

40.Also see, building licence for special conditions, if any.

Special Condition as per Labour Department of Government of Karnataka vide ADDENDUM (Hosakdag Hoodike) Letter No. LD/95/LET/2013, dated: 01-04-2013 :

1.Registration of Applicant / Builder / Owner / Contractor and the construction workers working in the construction site with the "Karnataka Building and Other Construction workers Welfare Board"should be strictly adhered to

2.The Applicant / Builder / Owner / Contractor should submit the Registration of establishment and list of construction workers engaged at the time of issue of Commencement Certificate. A copy of the same shall also be submitted to the concerned local Engineer in order to inspect the establishment and ensure the registration of establishment and workers working at construction site or work place.

3.The Applicant / Builder / Owner / Contractor shall also inform the changes if any of the list of workers engaged by him.

4.At any point of time No Applicant / Builder / Owner / Contractor shall engage a construction worker in his site or work place who is not registered with the "Karnataka Building and Other Construction workers Welfare Board".

Note :

1.Accommodation shall be provided for setting up of schools for imparting education to the children o f construction workers in the labour camps / construction sites.

2.List of children of workers shall be furnished by the builder / contractor to the Labour Department which is mandatory.

3.Employment of child labour in the construction activities strictly prohibited.

4.Obtaining NOC from the Labour Department before commencing the construction work is a must.

5.BBMP will not be responsible for any dispute that may arise in respect of property in question.

6.In case if the documents submitted in respect of property in question is found to be false or fabricated, the plan sanctioned stands cancelled automatically and legal action will be initiated.

COLOR INDEX

- PLOT BOUNDARY
- ABUTTING ROAD
- PROPOSED WORK (COVERAGE AREA)
- EXISTING (To be retained)
- EXISTING (To be demolished)

SCALE : 1:100

AREA STATEMENT (BBMP)	VERSION NO.: 1.0.3	
	VERSION DATE: 21/01/2021	
PROJECT DETAIL:		
Authority: BBMP	Plot Use: Residential	
Inward_No: PRJ/1271/21-22	Plot SubUse: MultiDwelling Units	
Application Type: General	Land Use Zone: Residential (Main)	
Proposal Type: Building Permission	Plot/Sub Plot No.:51/OLD 20/1(New Sy no 149),OLD 20/P1(New Sy no 138),OLD 20/5(New Sy no 148)	
Nature of Sanction: NEW	City Survey No.: 20/1(New Sy no 149),20/2 20/P1(New Sy no 138),20/5(New Sy no 148)	
Location: RING-III	Khata No. (As per Khata Extract): 51/OLD 20/1(New Sy no 149), OLD 20/P1(New Sy no 138),OLD 20/5(New Sy no 148)	
Building Line Specified as per Z.R: NA	Locality / Street of the property: KAMMANAHALLI VILLAGE, BEGUR HOBLI, BANGALORE. WARD NO 192	
Zone: Bommanahalli		
Ward: Ward-192		
Planning District: 321-Anjanapura		
AREA DETAILS:		SQ.MT.
AREA OF PLOT (Minimum)	(A)	32374.40
Deduction for NetPlot Area		
Road Widening Area		187.60
Total		187.60
Park & Open Space		3903.36
Area Reserved For Secondary Rajakaluve		661.45
Aree Reserved For 12M Road		2087.38
NET AREA OF PLOT	(A-Deductions)	32186.80
Deduction for Balance Plot Area		
Road Widening Area		187.60
Amenity Area		1619.03
Total		1806.63
BALANCE AREA OF PLOT	(A-Deductions)	30567.77
AREA OF PLOT Considered For Coverage		30099.43
AREA OF PLOT Considered For FAR		30755.40
COVERAGE CHECK		
Permissible Coverage area (55.00 %)		16554.68
Proposed Coverage Area (42.16 %)		12692.49
Achieved Net coverage area (42.16 %)		12692.49
Balance coverage area left (12.84 %)		3862.19
FAR CHECK		
Permissible F.A.R. as per zoning regulation 2015 (2.00)		61511.70
Additional F.A.R within Ring I and II (for amalgamated plot 2.00)		61511.70
Allowable TDR Area (60% of Perm.FAR)		0.00
Premium FAR for Plot within Impact Zone (-)		0.00
Total Perm. FAR area (2.00)		61511.70
Residential FAR (100.00%)		60545.79
Proposed FAR Area		60545.79
Achieved Net FAR Area (1.97)		60545.79
Balance FAR Area (0.03)		965.91
BUILT UP AREA CHECK		
Proposed BuiltUp Area		94907.83
Substructure Area Add in BUA (Layout Lvl)		15.00
Achieved BuiltUp Area		94922.83

Approval Date :

Block USE/SUBUSE Details

Block Name	Block Use	Block SubUse	Block Structure	Block Land Use Category
BLOCK 1 (BLOCK 1)	Residential	MultiDwelling Units	Bldg upto 14.95 mt. Ht.	R
BLOCK 2 (BLOCK 2)	Residential	MultiDwelling Units	Bldg upto 14.95 mt. Ht.	R
BLOCK 3 SOUTH AND WEST WING (BLOCK 3 SOUTH AND WEST WING)	Residential	MultiDwelling Units	Bldg upto 14.95 mt. Ht.	R

Required Parking(Table 7a)

Block Name	Type	SubUse	Area (Sq.mt.)	Units Reqd.	Units Prop.	Car Reqd./Unit	Car Reqd.	Car Prop.
BLOCK 1 (BLOCK 1)	Residential	MultiDwelling Units	0 - 50	2	-	1	14	-
			50 - 225	1	-	1	83	-
BLOCK 2 (BLOCK 2)	Residential	MultiDwelling Units	0 - 50	2	-	1	6.5	-
			50 - 225	1	-	1	109	-
BLOCK 3 SOUTH AND WEST WING (BLOCK 3 SOUTH AND WEST WING)	Residential	MultiDwelling Units	50 - 225	1	-	1	215	-
Total :							428	611

Parking Check (Table 7b)

Vehicle Type	Reqd. No.	Reqd. Area (Sq.mt.)	Achieved No.	Achieved Area (Sq.mt.)
Car	428	5885.00	611	8401.25
Visitor's Car Parking	44	605.00	0	0.00
Total Car	472	6490.00	611	8401.25
TwoWheeler	-	605.00	0	0.00
Other Parking	-	-	-	18180.44
Total		7095.00		26581.69

FAR &Tenement Details

Block	No. of Same Bldg	Total Built Up Area (Sq.mt.)	StairCase	Lift	Lift Machine	Void	Ramp	Parking	Proposed FAR Area (Sq.mt.) Resi.	Total FAR Area (Sq.mt.)	Tnmt (No.)	Carpet Area other than Tenement
BLOCK 1 (BLOCK 1)	1	15389.73	445.74	51.00	10.20	1225.86	0.00	0.00	13656.93	13656.93	111	0.00
BLOCK 2 (BLOCK 2)	1	46509.45	685.41	114.60	10.20	1548.22	501.59	26581.69	17067.75	17067.75	122	2260.86
BLOCK 3 SOUTH AND WEST WING (BLOCK 3 SOUTH AND WEST WING)	1	33008.65	641.29	123.00	14.40	2408.87	0.00	0.00	29821.09	29821.09	215	0.00
Grand Total	3	94907.83	1772.44	288.60	34.80	5182.95	501.59	26581.69	60545.77	60545.77	448.00	2260.86

OWNER / GPA HOLDER'S SIGNATURE

OWNER'S ADDRESS WITH ID NUMBER & CONTACT NUMBER :
NANDI HOUSING PRIVATE LTD
REP BY ITS DIRECTOR THOMAS.I OLLAPALLY
NO 46, 36TH MAIN, BTM DOLL
SCHEME, BANGALORE

ARCHITECT/ENGINEER /SUPERVISOR 'S SIGNATURE
LAKSHMIKANTHA S NO 58, 2ND CROSS, KATHRIGUPPA,
BENGALURU BCC/BL-3.6/E-442

GAYATHRI & NAMITH ARCHITECTS
BCC/BL-3.6/A-1877-08-09
KORAMANGALA, BANGALORE

PROJECT TITLE :
PROPOSED RESIDENTIAL APARTMENT BUILDING AT SITE/KATHA NO 51/OLD 20/1(New Sy no 149),OLD 20/P1(New Sy no 138), OLD 20/5(New Sy no 148) KAMMANAHALLI VILLAGE, BEGUR HOBLI, BANGALORE. WARD NO 192.

SHEET NO : 1 OF 5

SANCTIONING AUTHORITY :

ASSISTANT / JUNIOR ENGINEER / TOWN PLANNER	ASSISTANT DIRECTOR	DEPUTY DIRECTOR	JOINT DIRECTOR

This approval of Building plan/ Modified plan is valid for two years from the date of issue of plan and building licence by the competent authority.

SOUTH